

SURI VIDYASAGAR COLLEGE (Govt. Sponsored)
SURI, BIRBHUM

Ref. No: 313/2022

Date: 20/09/2022

Sealed quotations are invited from reputed contractor/construction agencies for renovation and construction of existing boundary wall & Fencing with Concertina coil as per specification given below. Last date of submission of quotation is 27/09/2022 up to 4pm to the college office. The contractor/agencies are requested to contact college office for further clarification.

Name of work: Renovation and construction of Existing Guard wall
and Fencing with Concertina coil
(Near Staff residence).

Amount of works: Approx 20 fts length.

- a) 1.5 ft height 5" brick works over existing wall with 1st class chimney bricks in cement mortar (1:4).
- b) 3"x 10" Tie casting above brick wall with 8mm rod.
- c) Plaster of bricks and concrete works with sand and cement mortar including all.
- d) 2.5 fts. M S angle above brick wall with 10 ft gap.
- e) Fencing with barbed fencing wire (concertina coil).

Agencies are requested to quote with all finish and specification of rod, brick, cement, fixing of M S angle etc used.



J. Panichg
Principal 20/09/2022

Suri Vidyasagar College
Principal.
Suri Vidyasagar College